


NUNAVUT

AERODROME / FACILITY DIRECTORY

ALERT NU

CYLT

REF	N82 31 02 W62 17 04 44°W (2022) UTC-5(4) Elev 100' A5050 LO9 HI1 CAP	
OPR	DND/1CdnAirDiv Alert AMO Ottawa 613-996-7741 CSN 996-7741 Mil PPR (min 7 days ntc) for foreign & civ acft 12-20Z± Mon-Fri, closed Sat, Sun & Cdn hols	
FLT PLN		
ACC MIL WX	Edmonton IFR 888-358-7526 on site IFR clnc for rtes entering Reykjavik airspace can be obtained by contacting +354-424-4264/4141 prior to dep fr Alert. Met brief for mil auth flt only. Lcl Met Section 613-945-3145/3146 ext 3250 ltd hrs. O/T JMC 1-800-WXMETEO (996-3836) or CSN 432-2613. METAR dur mil auth flt ops. TAF dur mil auth flt ops, issue times depending on mil requirements.	
SERVICES FUEL ARFF SUP FL	Only as auth on issued PPR CAT 4 D-Ice	
RWY DATA RCR	Rwy 05(048°T)/23(228°T) 5500x150 gravel Rwy 05 first 260' up 0.19%, next 660' down 0.83%, next 880' down 0.08%, next 1610' down 0.55%, last 2090' up 0.89%. Opr Strip plowed weekly. PCN	
LIGHTING	05-AO, 23-AN(non-std 2000') AS(HI) P2 2.7° GPI 733; O/R fr Thule exc win when lgts turned on upon receipt of Flt Pln. AMP3 lgt avbl Rwy 23. AMP3 marker panels avbl Rwy 05 (non-standard ldg zone marker panels, assault ldg zone dimensions 800ft, 300ft underrun included) & 23.	
COMM ATF MIL	All flts shall ctc Alert Metro 8816-5243-1431 via satellite phone if avbl 1 hr prior to ldg. tfc 126.7 5NM 3100 ASL All acft call Alert Metro within 20 min of ETA with load data. Alert Metro 126.7 5680 6706 11232	
NAV NDB TACAN	LT 305 (M) N82 31 33 W62 12 41 ULT 110.7 Ch 44 N82 31 02 W62 18 42 (72') oriented on True North	
PRO	Circling rstd to area NW rwy centreline. Prkg: Follow gnd marshaller's instructions. Ctc 126.7 prior to start up. All acft shall advs SMOKEY on 126.7 prior to engine start in order to guarantee the ramp is free of non-essential gnd vehicles & personnel.	
CAUTION	Dly radiosonde balloon launches with an ascent rate of 1000 ft/min btwn the hrs of 1115Z-1345Z & 2315Z-0145Z. Sharp drop-off east of Thld 23. Aprons immediately adjacent rwy at Thld 05. Acft may be parked close proximity to rwy both sides.	